सत्यमेव जयते

File No: 2-11/PCC/EIA Notfn./2026

State Environment Impact Assessment Authority (SEIAA), Andaman And Nicobar Islands

(Constituted as per the provision of EIA Notification, 2006, as amended by the Ministry of Environment, Forest and Climate Change, Government of India)

Dated **02/11/2026**

To,

The Deputy Commissioner
North And Middle Andaman, Andaman And Nicobar Islands, 744204
nmadc.and@nic.in

Subject: Grant of prior Environmental Clearance (EC) to the proposed Mining Project under the provisions of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application submitted to SEIAA vide proposal number SIA/AN/MIN/594753/2026 dated 07/10/2026 for grant of prior Environmental Clearance (EC) to the project under the provision of the EIA Notification 2006-and as amended thereof.

2. The particulars of the proposal are as below :

(i) EC Identification No.	EC26C0108AN5901857N
(ii) File No.	2-11/PCC/EIA Notfn./2026
(iii) Clearance Type	Mining EC Under 5 Ha
(iv) Category	B2
(v) Project/Activity Included Schedule No.	1(a) Mining of minerals
(vii) Name of Project	Environmental Clearence for Panchawati Quarry Rangat
(viii) Location of Project (District, State)	NORTH AND MIDDLE ANDAMAN, ANDAMAN AND NICOBAR ISLANDS
(ix) Issuing Authority	UTEIAA
(x) Applicability of General Conditions	Yes

Project Salient Features

The details of the proposed quarry blocks, as indicated in the Quarry Plans dated 06.10.2026 submitted by the Project Proponent for the Madhupur, Shyamnagar, Harinagar and Panchawati Quarry Sites in North and Middle Andaman District are summarised below:

S No.	Name of Quarry Site	Survey No. and Total Area	Total Area of Proposed Blocks	Details of Proposed Quarry Blocks	GPS Coordinates
1	Madhupur Quarry site, Diglipur	49/P Area-33.03Ha	2 Ha	8 Blocks- A,B,C,D,E,F,G and H having area of 0.25 Hectares each out of the land bearing Sy No.49/P of area 33.03 hectares for conduct of stone quarrying without use of explosives	13°16’14’’N 92°57’50’’E
2	Shyamnagar Quarry Site, Diglipur	102/1/P (Area: 1Ha) (102/1 Area: 10.26 Ha)	0.75 Ha	3 Blocks- B,C,D having area of 0.25 Hectares in the Sy No. 102/P of area 1 Ha out of the land bearing Sy No.102/1 of area 10.26 hectares for conduct of stone quarrying without use of explosives	13°23’42’’N 92°55’18’’E
3	Harinagar Quarry Site, Mayabunder	4/1/P 99.74 Ha	2 Ha	8 Blocks- A,B,C,D,E,F,G and H1 having area of 0.25 Hectares out of the land bearing Sy No.4/1/P of area 99.74 hectares for conduct of stone quarrying without use of explosives	12°41’17’’N 92°52’23’’E
4	Panchawati Quarry site, Rangat	49/1 Area-17.85 Ha	0.5 Ha	2 Blocks-E,F having area of 0.25 Hectares out of the land bearing Sy No.49/1/P of area 17.85 Ha hectares for conduct of stone quarrying without use of explosives	12°34’02’’N 92°57’00’’E

General Conditions

1. In view of the particulars given in the Para 1 above, the project proposal interalia including Form-2(Part A, B and C)/ Reports were submitted to the UTEIAA for an appraisal by the UTEIAA under the provision of EIA notification 2006 and its subsequent amendments.
2. The above-mentioned proposal has been considered by UTEIAA in the 8th meeting held on 27/10/2026. The minutes of the meeting and all the project documents are available on PARIVESH portal which can be accessed from the PARIVESH portal by scanning the QR Code above.
3. The UTEAC, in its 15th meeting held on 13/10/2026, based on information submitted viz: Form 1 (Part A, B and C), reports etc & clarifications provided by the project proponent and after detailed deliberations on all technical aspects and compliance thereto furnished by the Project Proponent, recommended the proposal for grant of Environment Clearance under the provision of EIA Notification, 2006 and as amended thereof subject to

stipulation of Specific and Standard EC conditions as detailed in Annexure-I.

4. The UTEIAA has examined the proposal in accordance with the provisions contained in the Environment Impact Assessment (EIA) Notification, 2006 & further amendments thereto and based on the recommendations of the UTEAC hereby accords Environment Clearance for the instant proposal to the Project Proponent- The Deputy Commissioner, North and Middle Andaman district under the provisions of EIA Notification, 2006 and as amended thereof subject to compliance of the Specific and Standard EC conditions as given in Annexure I.
5. The Ministry reserves the right to stipulate additional conditions, if found necessary.
6. The Environmental Clearance to the aforementioned project is under provisions of EIA Notification, 2006. It does not tantamount to approvals/consent/permissions etc. required to be obtained under any other Act/Rule/regulation. The Project Proponent is under obligation to obtain approvals /clearances under any other Acts/ Regulations or Statutes, as applicable, to the project.
7. The PP is under obligation to implement commitments made in the Quarry Plan, during presentation to the UTEAC, which forms part of this EC.
8. Validity of EC is upto 06/10/2029 from which the prior environmental clearance is granted by the regulatory authority.
9. This is issued with the approval of the Competent Authority.

Copy To

1. The Chairman, Union territory of Andaman and Nicobar Islands Environment Impact Assessment Authority (UTEIAA) , Dr R S C Jayaraj Ifs Retd. Principal Chief Conservator Of Forests “Al-204 Harihar Paradise Netaji Road P.N. Pudur , Coimbatore, Tamil Nadu, rsc.jayaraj@gmail.com
2. The Chairman, Union territory of Andaman and Nicobar Islands Expert Appraisal Committee (UTEAC), Scientist F/Officer-In-Charge Atal Centre For Ocean Science And Technology For Islands National Institute Of Ocean Technology , South Andamans, Andaman And Nicobar Islands, dilip.niot@gov.in
3. The Joint Secretary (Environment), Ministry of Environment Forests and Climate Change Govt. of India., Indira Paryavaran Bhavan Jor Bagh Road Aliganj New Delhi- 110003, New Delhi, Delhi, sahnk@cag.gov.in
4. The Addl. Principal Chief Conservator of Forests (C), Regional Office, Ministry Of Environment Forest And Climate Change Regional Office (Sez) Ist And Iind Floor Handloom Export Promotion Council 34 Cathedral Garden Road Nungambakkam Chennai - 34 , Chennai, Tamil Nadu, ro.moefccc@gov.in
5. The Principal Chief Conservator of Forests Andaman and Nicobar Islands, Department of Environment and Forests, Van Sadan Haddo Sri Vijayapuram, South Andamans, Andaman And Nicobar Islands, pccfani@gmail.com
6. The Secretary, (Environment and Forest), Secretariat Andaman And Nicobar Administration, South Andamans, Andaman And Nicobar Islands, secretary-home-ani@and.nic.in
7. The Chairman, Andaman and Nicobar Pollution Control Committee (ANPCC), Department Of Science & Technology Dollygunj Sri Vijayapuram , South Andamans, Andaman And Nicobar Islands, secretary-svpmc@gov.in
8. The Divisional Forest Officer Mayabunder, Department of Environment and Forests, ., North And Middle Andaman, Andaman And Nicobar Islands, dfo.mb305@and.nic.in
9. The Divisional Forest Officer Middle Andaman, Department of Environment and Forests , ., North And Middle Andaman, Andaman And Nicobar Islands, dfoma.and@nic.in
10. The Divisional Forest Officer Diglipur, Department of Environment and Forests, ., North And Middle Andaman, Andaman And Nicobar Islands, dfo-dp103192-23@and.nic.in

Annexure 1

Specific EC Conditions for (Mining Of Minerals)

1. Conditions Specified By Union Territory Environment Impact Assessment Authority (Uteiaa)

S. No	EC Conditions
1.1	a) Validity of Environment Clearance The validity of the Environmental Clearances shall be up to 06.10.2029, in line with the validity of the approved Quarry Plan vide No. 46-56/DC(N&MA)/QP/2022 dated 06-10-2026. The extraction of minor minerals shall be restricted to the annual production capacities of upto 12000 cbm of minor mineral from each block per annum and shall, in no case, exceed the estimated stone volume assessed for the respective quarry block or the permissible production capacity stipulated in the approved Quarry Plan. b) Reclamation and Restoration of Older Quarry Sites The Project Proponent shall prepare a phase-wise plan for the reclamation and Restoration of all such previously quarried areas falling within the same survey numbers as the proposed quarry sites, in consultation with the Forest Department. The areas concerned are as follows: i. Madhupur: Survey No. 49/P, covering an area of 33.03 ha. ii. Shyamnagar: Survey No. 102/1, covering an area of 10.26 ha. iii. Harinagar: Survey No. 4/1/P, covering an area of 99.74 ha. iv. Panchawati: Survey No. 49/1/P, covering an area of 17.85 ha. The Progress of Implementation of reclamation and restoration plan shall be submitted along with each six-monthly compliance report. The report shall indicate , at a minimum, the following: 1. Geo-referenced maps showing survey boundaries, quarry areas, abandoned pits and adjoining Reserved Forest boundaries. 2. Survey-based details of previously quarried, reclaimed and unreclaimed areas with supporting maps and area calculations. 3. Existing site conditions, including pits, slopes, vegetation, drainage and erosion. 4. Phase-wise reclamation plan covering stabilisation, backfilling, drainage, plantation of native species, proposed land use, timeline and estimated cost. 5. Monitoring and maintenance plan specifying performance indicators, inspection frequency, vegetation survival targets and corrective measures. 6. Geo-tagged photographs and a site-wise progress statement indicating area reclaimed, percentage completed and balance area remaining. 7. Phase-wise implementation targets, financial provisions and the proposed completion schedule. c) Demarcation of Reserved Forest boundary The boundary of the Reserved Forest adjoining the proposed quarry sites, wherever they fall close to the revenue-forest boundary, shall be physically surveyed and clearly demarcated by the concerned Divisional Forest Officer (DFO), using appropriate markings such as paint markings, poles or other suitable means, prior to the commencement of quarrying operations. The Project Proponent shall ensure that no quarrying or allied activities are undertaken within the Reserved Forest area. The demarcated boundary shall be duly communicated to the contractors to ensure strict compliance.

2. Conditions Specified By Union Territory Expert Appraisal Committee (Uteac)---

S. No	EC Conditions
2.1	1. Routine surveillance and periodic on-site verification must be consistently carried out by the office of Deputy Commissioner (North and Middle Andaman) at all quarry sites to ensure extraction of quarry materials adheres to permitted values and that no illicit mining activities take place at the sites. 2. Adequate Fencing and proper signboards shall be installed at quarry locations to prevent unauthorised entry and trespassing by animals and local residents. 3. Monthly Reports of stone extraction along with geo-tagged photographs shall be submitted by

S. No	EC Conditions
	project proponent and shall form the part of Six-Monthly compliance reports. 4. The Mitigation measures prescribed in the Quarry Plan, i.e. Progressive and Final Closure Plan, Plan for Reclamation & Restoration of land, and Measures for Pollution Control shall be implemented at all sites, with appropriate indicators to demonstrate their effectiveness. 5. All the proposed quarry sites shall be restored after completion of extraction to a condition suitable for regeneration of flora and fauna. Restored or abandoned quarry areas may subsequently be utilized for appropriate beneficial purposes. 6. Plantation activities to be carried out by Local Administration in all quarry sites in consultation with Forest department. 7. Member Secretary UTEAC or Member Secretary ANPCC shall nominate a team of officials to conduct site inspections and cross-verify the compliance reported by the Project Proponent following submission of each six-monthly compliance report. The District Administration shall provide all necessary assistance in this regard.

Standard EC Conditions for (Mining of minerals)

1. Statutory Compliance

S. No	EC Conditions
1.1	The Project proponent complies with all the statutory requirements and judgment of Hon'ble Supreme Court dated 2nd August, 2017 in Writ Petition (Civil) No. 114 of 2014 in matter of Common Cause versus Union of India &Ors before commencing the mining operations.
1.2	The Project Authorities should widely advertise about the grant of this EC letter by printing the same in at least two local newspapers, one of which shall be in vernacular language of the concerned area. The advertisement shall be done within 7 days of the issue of the clearance letter mentioning that the instant project has been accorded EC and copy of the EC letter is available with the State Pollution Control Board/Committee and web site of the Ministry of Environment, Forest and Climate Change (www.parivesh.nic.in). A copy of the advertisement may be forwarded to the concerned MoEFCC Regional Office for compliance and record.
1.3	This Environmental Clearance (EC) is subject to orders/ judgment of Honble Supreme Court of India, Honble High Court, Honble NGT and any other Court of Law, Common Cause Conditions as may be applicable.
1.4	The copies of the environmental clearance shall be submitted by the project proponent to the Heads of local bodies/Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.
1.5	The project proponent shall obtain Consent to Establish / Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the Andaman and Nicobar Pollution Control Committee(ANPCC).
1.6	Permission of power supply to be taken from the concerned authority for meeting power demand of the project site.

2.

S. No	EC Conditions
2.1	The Project Proponent shall carryout plantation/ afforestation in backfilled and reclaimed area of mining lease, around water body, along the roadsides, in community areas etc. by planting the native species in consultation with the Forest Department/ Agriculture Department/ Rural development department/ Tribal Welfare Department/ Gram Panchayat such that only those species be selected which are of use to the local people. Adequate budgetary provision shall be made for protection and care of trees.
2.2	The maximum production or peak production at any given time shall not exceed the limit as prescribed in the EC
2.3	The project proponent shall obtain all requisite statutory clearances from competent authorities prior to commencement of operations.
2.4	Extraction/Quarrying of Stone upto production capacity specified in the Environment Clearance is permitted. No extraction of mineral, other than stone quarry is permitted at the quarry site.
2.5	The quarry should not be operated between 6.00 pm and 6.00am.
2.6	The location of the quarry site shall be as per the Quarry plan and no change, deviation or alteration that may affect the environment, extend and location of the quarry shall be made. The Project proponent shall ensure the same through formal undertaking.
2.7	Quantity of material extracted along with Periodic site photographs with Date, Time & Coordinates shall be submitted to ANPCC six-monthly by proponent and also form part of the six-monthly compliance report submitted in respect of Environmental Clearance issued by UTEIAA.
2.8	The Project Proponent shall comply with the directions that the ANPCC may issue from time to time regarding prevention and control of air, water, land and noise pollution.
2.9	After excavation at the site is completed, the land may be used for rain water harvesting with protective barriers/any other suitable approved purpose or may be reclaimed.
2.10	The project proponent shall maintain records pertaining to water consumption, production, and waste generation, and produce the same for inspection as required.
2.11	Waste Management 1. All solid waste generated within the premises shall be systematically collected, stored, and disposed of in an environmentally sound manner 2. The unit shall not use banned ‘use and throwaway plastics’ such as plastic sheets used for food wrapping, plastic plates, plastic coated tea cups, plastic tumbler, water pouches and packets, plastic straw, and plastic bags irrespective of thickness, within the industry premises. Instead, the unit shall promote eco-friendly alternatives such as biodegradable materials, reusable containers, and sustainable packaging options 3. Any other waste, if generated, may be disposed off as per the applicable existing rules and acts.

3. Air Quality Monitoring And Preservation

S. No	EC Conditions
3.1	Adequate Water sprinkling arrangements shall be provided at all haul roads, transportation roads, quarry areas, stack yard and other dust generating points to control fugitive dust emission.
3.2	Wet drilling is to be adopted to control dust emission. Drilling shall be done only by licensed agent of the proponent after obtaining required approvals from competent authorities.
3.3	Loading and unloading activities including all transfer points should have efficient dust control system arrangements.
3.4	The Concentration of particulate matter (PM 10) in ambient air at the boundary shall not exceed 100 µg/m3
3.5	The Concentration of particulate matter (PM2.5) in ambient air at the boundary shall not exceed 60 µg/m3
3.6	The suspended particulate matter measured between 3 metres and 10 metres from any process equipment of the unit shall not exceed 600 microgrammes per cubic metre.
3.7	It shall be the responsibility of the Project Proponents to monitor and submit six-monthly report w.r.t the Air Quality Emission Standards at the location.

4. Water Quality Monitoring And Preservation

S. No	EC Conditions
4.1	Surface runoff shall be properly channelized and allowed to flow to natural drainage course without causing erosion, siltation, or contamination outside the lease area.
4.2	Mining operations must not result in any form of groundwater contamination. Groundwater quality monitoring shall be conducted once every six months, and reports shall be submitted to ANPCC. The same shall also form part of the six-monthly compliance report submitted in respect of Environmental Clearance issued by UTEIAA.
4.3	In case, immediate mining scheme envisages intersection of ground water table, then Environmental Clearance shall become operational only after receiving formal clearance from CGWA. In case, mining operation involves intersection of ground water table at a later stage, then PP shall ensure that prior approval from CGWA is in place before such mining operations. The permission for intersection of ground water table shall essentially be based on detailed hydro-geological study of the area.
4.4	The monitoring data shall be uploaded on the Project Proponent website and displayed at the project site at a suitable location. The circular No.J-20012/1/2006-1A.11 (M) dated 27th May, 2009 issued by Ministry of Environment, Forest and Climate Change shall also be referred in this regard for its compliance.
4.5	Ground water, excluding mine water, shall not be used for mining operations. Rainwater harvesting shall be implemented for conservation and augmentation of ground water resources.

5. Noise And Vibration Monitoring And Prevention

S. No	EC Conditions
5.1	The Project Proponent shall take measures for control of noise levels below 85 dBA in the work environment. The workers engaged in operations of HEMM, etc. should be provided with ear plugs /muffs. All personnel including laborers working in dusty areas shall be provided with protective respiratory devices along with adequate training, awareness and information on safety and health aspects. The PP shall be held responsible in case it has been found that workers/ personals/ laborers are working without personal protective equipment.
5.2	The sound level (Leq) at 1 m outside the boundary of the site should not exceed the ambient noise standard applicable to the adjoining areas.
5.3	The workers shall be provided with appropriate personal protective equipment viz. ear mufflers/ ear plug or noise proof cabins and the noise generated during operation should conform to the standards prescribed under The Noise Pollution (Regulation and Control) Rules, 2000 viz. 75 dBA (day time)

6. Mining Plan

S. No	EC Conditions
6.1	The land-use of the mine lease area at various stages of mining scheme as well as at the end-of-life shall be governed as per the approved Mining Plan. The excavation vis-à-vis backfilling in the mine lease area and corresponding afforestation to be raised in the reclaimed area shall be governed as per approved mining plan. PP shall ensure the monitoring and management of rehabilitated areas until the vegetation becomes self-sustaining. The compliance status shall be submitted half-yearly to the UTEIAA and ANPCC.
6.2	The Project Proponent shall adhere to approved mining plan, inter alia, including, total excavation (quantum of mineral, waste, over burden, inter burden and top soil etc.); mining technology; lease area; scope of working (method of mining, overburden & dump management, O.B& dump mining, mineral transportation mode, ultimate depth of mining, concurrent reclamation and reclamation at mine closure; land-use of the mine lease area at various stages of mining scheme as well as at the end-of-life; etc.).
6.3	Efforts should be made to reduce energy and fuel consumption by conservation, efficiency improvements and use of renewable energy.

7. Land Reclamation

S. No	EC Conditions
7.1	The Overburden (O.B.), waste and topsoil generated during the mining operations shall be stacked at earmarked OB dump site(s) only and it should not be kept active for a long period of time. The physical parameters of the OB / waste dumps / topsoil dump like height, width and angle of slope shall be governed as per the approved Mining Plan and the guidelines/circulars issued by D.G.M.S. The topsoil shall be used for land reclamation and plantation.
7.2	Regular monitoring of subsidence movement on the surface over and around the working areas and its impact on natural drainage pattern, water bodies, vegetation, structure, roads and surroundings shall be

S. No	EC Conditions
	continued till movement ceases completely. In case of observation of any high rate of subsidence beyond the limit prescribed, appropriate effective mitigation measures shall be taken to avoid loss of life and materials. Cracks should be effectively plugged in with ballast and clay soil/suitable material.
7.3	Thorough inspection of the mine lease area for any cracks developed at the surface due to mining activities below ground shall be carried out to prevent inrush of water in the mine.
7.4	Native tree species shall be selected and planted over areas affected by subsidence.

8. Public Hearing And Human Health Issues

S. No	EC Conditions
8.1	Project Proponent shall make provision for the housing for workers/labors or shall construct labor camps within/outside (company owned land) with necessary basic infrastructure/ facilities like fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche for kids etc. The housing may be provided in the form of temporary structures which can be removed after the completion of the project related infrastructure. The domestic waste water should be treated with STP in order to avoid contamination of underground water.
8.2	Adequate illumination shall be ensured in all mine locations (as per DGMS standards) and monitored
8.3	Personnel (including outsourced employees) working in core zone shall wear protective respiratory devices and shall also be provided with adequate training and information on safety and health aspects.
8.4	Effective arrangement shall be made to provide and maintain at suitable points conveniently situated, a sufficient supply of drinking water for all the persons employed.

9. Miscellaneous

S. No	EC Conditions
9.1	Concealing factual data failure to comply with any or submission of false/ fabricated data and of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.
9.2	The Ministry or any other competent authority may alter/modify the above conditions or stipulate any further condition in the interest of environment protection.
9.3	The above conditions will be enforced inter-alia, under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and the Public Liability Insurance Act, 1991 along with their amendments and rules made there under and also any other orders passed by the Hon’ble Supreme Court of India/High Court and any other Court of Law relating to the subject matter.

S. No	EC Conditions
9.4	The Project Proponent shall submit Six-Monthly Compliance Reports with respect to the stipulated terms and conditions of the Environmental Clearance through the PARIVESH portal & to the concerned Regional Office of MoEF&CC, Union Territory of Andaman and Nicobar Islands Environment Impact Assessment Authority (UTEIAA), and Andaman and Nicobar Pollution Control Committee (ANPCC). The acknowledgements generated upon online submission of the six-monthly compliance reports through the PARIVESH portal shall be retained by the Project Proponent for future reference.
9.5	The concerned Regional Office of the MoEF&CC shall randomly monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the MoEF&CC officer(s) by furnishing the requisite data / information / monitoring reports.
9.6	Any appeal against this environmental clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
9.7	In pursuant to Ministrys O.M No 22-34/2018-IA.III dated 16.01.2020 to comply with the direction made by Honble Supreme Court on 8.01.2020 in W.P. (Civil) No 114/2014 in the matter Common Cause vs Union of India, the mining lease holder shall after ceasing mining operations, undertake regrassing the mining area and any other area which may have been disturbed due to other mining activities and restore the land to a condition which is fit for growth of fodder, flora, fauna etc.
9.8	The proponent shall abide by all the commitments and recommendations made in the Quarry plan and also that during presentation to the UTEAC.

Additional EC Conditions

N/A

Annexure 2

Details of the Project

<table>
<tr><th>S. No.</th><th>Particulars</th><th>Details</th></tr>
<tr><td>a.</td><td>Details of the Project</td><td>Environmental Clearence for Panchawati Quarry Rangat</td></tr>
<tr><td>b.</td><td>Latitude and Longitude of the project site</td><td>12.5709815121703,92.9554844775571
12.5734729804863,92.959665410079</td></tr>
<tr><td>c.</td><td>Land Requirement (in Ha) of the project or activity</td><td>
<table>
<tr><th>Nature of Land involved</th><th>Area in Ha</th></tr>
<tr><td>Non-Forest Land (A)</td><td>0.5</td></tr>
<tr><td>Forest Land (B)</td><td>0</td></tr>
</table>
</td></tr>
</table>

S. No.	Particulars	Details
		<table><tr><th>Nature of Land involved</th><th>Area in Ha</th></tr><tr><td>Total Land (A+B)</td><td>0.5</td></tr></table>
d.	Date of Public Consultation	Public consultation for the project was held on
e.	Rehabilitation and Resettlement (R&R) involvement	NO
f.	Project Cost (in lacs)	80
g.	EMP Cost (in lacs)	
h.	Employment Details	

Details of Minerals Products & By-products

Name of the Mineral to be mined	Classification of mineral [Major/Minor]	Production capacity in MTPA	Remarks
Stone Aggregate	Minor	0.0384	12000 CBM per block per year

Signature Not Verified

Digitally Signed by : Shri Rakesh Das
Member Secretary, SEIAA

Date: 02/11/2026